

# WATER WELL REPORT

State of Washington Date Printed 31-Jul 2003 Log No  
Construction/Decommission Original Construction 22103  
Construction Notice of Intent # 138688

CURRENT  
Notice of Intent No W168787  
Unique Ecology Well I D No AHG412  
Water Right Permit Number

OWNER DISQUE DON  
OWNER ADDR PO BOX 217 ORIENT WA 99160  
Well Street Address 3349 U ROCK CUT RD  
City Kettle Falls WA 99141 County STEVENS  
Location NE 1/4 NW 1/4 Sec 14 T 39 R 36E EWM  
Lat/Long N 5 Govt Lot 1 Lat Deg  
(s t r still) Lat Min/Sec  
REQUIRED Long Deg Long Min/Sec  
Tax Parcel No 1533800

<b>PROPOSED USE DOMESTIC</b>			
<b>TYPE OF WORK</b> Owners s Well Number (If more than one well) 1 <b>NEW WELL</b> Method <b>ROTARY</b>			
<b>DIMENSIONS</b> Diameter of well 6 inches Drilled 158 ft Depth of completed well 158 ft			
<b>CONSTRUCTION DETAILS</b>		Casing installed <b>WELDED</b>	
Liner installed		6 Dia from +2 ft to 155 ft	
Dia from ft to ft		Dia from ft to ft	
Dia from ft to ft		Dia from ft to ft	
<b>Perforations</b> No Used In Type of perforator used SIZE of perforations in by in Perforations from ft to ft Perforations from ft to ft Perforations from ft to ft			
<b>Screens</b> Yes K Pac Location Manufacture s Name JOHNSON Type SLOTTED Model No STAINLESS Diam 5 slot size 10 from 154 ft to 158 ft Diam slot size from ft to ft			
<b>Gravel/Filter packed</b> No Size of Gravel Material placed from ft to ft			
<b>Surface seal</b> Yes To what depth 18 ft Seal method Material used in seal BENTONITE Did any strata contain unusable water? No Type of water Depth of strata Method of sealing strata off			
<b>PUMP</b> Manufacture s name Type H P 0			
<b>WATER LEVELS</b> Land surface elevation above mean sea level 0 ft Static level 20 ft below top of well Date 07/18/2003 Artesian Pressure lbs per square inch Date Artesian water controlled by			
<b>WELL TESTS</b> Drawdown is amount water level is lowered below static level Was a pump test made? No If yes by whom? Yield gal/min with ft drawdown after Yield gal/min with ft drawdown after Yield gal/min with ft drawdown after Recovery data (time taken as zero when pump turned off)(water level measured from well top to water level) Time Water Level Time Water Level Time Water Level Date of test Bailer test gal/min ft drawdown after hrs Air test 30 gal/min w/ stem set at 156 ft for 1 hours Artesian flow gpm Date Temperature of water Was a chemical analysis made? No			

<b>CONSTRUCTION OR DECOMMISSION PROCEDURE</b>		
Formation Describe by color character size of material and structure Show thickness of aquifers and the kind and nature of the material in each stratum penetrated Show at least one entry for each change in formation		
Material	From	To
SAND BROWN	0	8
SAND GRAVEL W/CLAY	8	18
BLUE CLAY DENSE	18	120
BLUE SILT SAND CLAY	120	142
GRAY SAND FINE TO MEDIUM W/WATER	142	158

SEP - 5 2003

Notes  
TOTAL GPM = 30+

Work started 07/17/2003 Completed 07/18/2003

**WELL CONSTRUCTION CERTIFICATION**  
I constructed and/or accept responsibility for construction of this well and its compliance with all Washington well construction standards Materials used and the information reported are true to my best knowledge and belief  
☒ Driller ☐ Engineer ☐ Trainee  
Name RONALD HURN License No 2258  
Signature Ronald Hurn  
If trainee Licensed driller is License No  
Licensed Driller Signature

**Drilling Company**  
NAME FOGLE PUMP & SUPPLY INC Shop COLVILLE  
ADDRESS 316 W 5TH  
Colville WA 99114  
Phone 509-684 2569 Toll Free 800-533-6518  
E Mail jrs@foglepump.com  
FAX 509-684-3032 WEB Site www.foglepump.com  
Contractor's  
Registration No FOGLEPS095L4 Date Log Created 07/31/2003

The Department of Ecology does NOT Warranty the Data and/or the Information on this Well Report.

house

Well ID# A116-412

Phone

285-9949

5145

# Fogle Pump & Supply, Inc.

## Customer Pump & System Record

Name Don Disque KEVIN WRIGHT Date 11-19-07  
Address 3349-F Rockcut Rd.  
Well Billing Address PO Box 217 Orient Va 22450  
Legal Description 1/4 1/4 SECT T R  
Water Use, Domestic X Irrigation        Subdivision        Other         
Well Depth 160' ID 6" GPM 30 Static         
Pump Brand SQE GRUNDFOS New - Used  
Pump Model # F1541014PV-52 15SQE15C-290 GPM        PSI         
Pump Serial # Send Handler Date Code         
Motor Brand Franklin New - Used  
Motor HP 1 1/2 Volts 230 Phs 3  
Motor Serial # 12 2076 Date Code 02D18  
Warranty #        5 yr.        1 yr.        None         
Pump Protector Type INTERNA Brand        Model         
Tank Brand IN WELL NT40SS Model        Warranty        yrs.  
Pump Setting 100' pipe Pipe Size 1" Pipe Type Sch 80 pipe  
Wire in well Size 12-4 Type Sub  
Pitless Size 1" PA Brand Dickas  
Well House        Pit        Other, Explain         
Distance to House 10' Elevation AD Pipe Size & Type 1" SCH.40  
Distance to Power Supply        Wire Size & Type       

### 15 SQE15-290


WWW.GRUNDFOS.COM

**PUMP COMPLETE**



**1x200-240V**

**11,7 A**



**7.1 kg / 15.7 lb**

**P1 0719 MADE IN DENMARK**

# 96160195

INSIDE WASHROOM

Installed By B.C. J.B.

Electrical By       

CUSTOMER

PUT CONTROLLER IN HOUSE THAT  
IS OPEN W/OUT OUTDOOR BOX

Invoice # 271139