




125 N. Park Ave. Deer Park, WA 99006 • (509) 276-1080 • (800) 772-4901

PUMP TEST CERTIFICATION FORM

PROPERTY OWNER: Duval, Scott		
PARCEL NUMBER: 2348610		
SITE ADDRESS: 3089 Hwy 25 N Northport		
SITE COUNTY: Stevens		
WATER SOURCE:	☒ DRILLED WELL	☐ SPRING / SURFACE WATER
		WELL TAG ID: BNP-272
PUMP TEST COMPLETED BY: Zachary Lunsford		DATE OF PUMP TEST: 2/2/2023
I certify that this water source was pump tested. The actual pump test rate was <u>26</u> gallons per minute.		
 Signature of Licensed Well Driller or Pump Installer		<u>2-3-2023</u> Date



125 N. Park Ave. Deer Park, WA 99006 • (509) 276-1080 • (800) 772-4901

Well Test Data Collection Form

Date of Test	2/2/2023	Owner	Duval, Scott
Well Construction	Drilled 6" Cased	Name of Well	Domestic
Well Depth	118'	Well Tag #	BNP-272
Static Water Level	50'	Job Location	3082 Hwy 25 N
GPM Driller Tested	30+ GPM	Parcel #	2348610
Test Pump Used	1.5HP 15 GPM 10	Pitless/Pumphouse	N/A
Pump Setting	100'	Condition	New
Pipe Size 1 1/4 PVC	Wire Size #12 awg	Pressure Tank Size	N/A
Observer	Zachary Lunsford	Electrical Controls	Control Box

Clock Time	Elapsed Time	Sounder Reading	Pumping Rate/GPM	PSI	Water Quality	Observation & Notes (initial all comments/verifications)
11:00 AM		50'	3	170	Poor	Dark orange/black no sediment
11:05 AM	5	52'	10	150	Poor	Dark orange/black no sediment
11:10 AM	5	52'	15	130	Poor	Bright orange/red no sediment
11:15 AM	5	52'	15	130	Poor	Light orange light sand
11:20 AM	5	52'	16.78	120	Poor	Light orange light sand
11:25 AM	5	53'	16.78	120	Poor	Light orange light sand
11:30 AM	5	53'	16.78	120	Poor	Light orange light sand
11:45 AM	15	53'	19.6	100	Poor	Light tan/orange no sediment
12:00 PM	15	54'	20.27	90	Poor	Light tan/orange no sediment
12:15 PM	15	54'	22.15	80	Poor	Light tan/orange no sediment
12:30 PM	15	54'	23.02	70	Poor	Light tan/orange no sediment
12:45 PM	15	54'	24.15	60	Fair	Orange tint no sediment
1:00 PM	15	54'	26.22	50	Fair	Orange tint no sediment
1:15 PM	15	54'	26.46	40	Fair	Orange tint no sediment
1:30 PM	15	54'	26.46	40	Fair	Orange tint no sediment
1:45 PM	15	54'	26.46	40	Fair	Orange tint no sediment
2:00 PM	15	54'	26.46	40	Fair	Orange tint no sediment
2:15 PM	15	54'	26.46	40	Fair	Orange tint no sediment
2:30 PM	15	54'	26.46	40	Fair	Orange tint no sediment
2:45 PM	15	54'	26.46	40	Fair	Collected samples
3:00 PM	15	54'	26.46	40	Fair	