

WATER WELL REPORT

State of Washington Date Printed: 07-Jun-2010 Log No. 0
 Construction / Decommission: Original Construction
 Construction Notice of Intent #: 392928

CURRENT
 Notice of Intent No.: WE11409
 Unique Ecology Well I.D. No. BBL772
 Water Right Permit Number:

RECEIVED
 AUG 20 2010

OWNER: SCHNEIDER, ADAM & ROSALIE
 OWNER ADDR 3383 SOUTH WAPATO ROAD, STERN REGIONAL OFFICE
 WAPATO, WA 98951

Well Add: 1496-U HIGHWAY 20 EAST

City: Colville, WA 99114 County: Stevens
 Location: SE 1/4 SE 1/4 Sec 21 T 35 R 41E EWM
 Lat/Long: Lat Deg Lat Min/Sec
 (s, t, r still) Long Deg Long Min/Sec
 REQUIRED)
 Tax Parcel No.: 5632400

PROPOSED USE: DOMESTIC	
TYPE OF WORK: Owners's Well Number: (If more than one well) NEW WELL Method: ROTARY	
DIMENSIONS: Diameter of well: 6 inches Drilled 600 ft. Depth of completed well 600 ft.	
CONSTRUCTION DETAILS:	Casing installed: WELDED
Liner installed: PVC 4 " Dia from 20 ft. to 600 ft.	6 " Dia from +2 ft. to 158 ft. " Dia from ft. to ft. " Dia from ft. to ft.
Perforations: Yes Used In: LINER Type of perforator used SKILL SAW SIZE of perforations 1/8 in. by 6 in. 100 Perforations from 480 ft. to 600 ft. Perforations from ft. to ft. Perforations from ft. to ft.	
Screens: 0 K-Pac Location: Manufacture's Name Type: Model No. Diam. slot size: from ft. to ft. Diam. slot size: from ft. to ft.	
Gravel/Filter packed: No Size of Gravel Material placed from ft. to ft.	
Surface seal: Yes To what depth 18 ft. Seal method: Material used in seal BENTONITE Did any strata contain unusable water? No Type of water: Depth of strata Method of sealing strata off	
PUMP: Manufacture's name Type: H.P. 0	
WATER LEVELS: Land-surface elevation above mean sea level: 0 ft. Static level 240 ft. below top of well Date 05/24/2010 Artesian Pressure lbs per square inch Date Artesian water controlled by	

CONSTRUCTION OR DECOMMISSION PROCEDURE		
Formation: Describe by color, character, size of material and structure. Show thickness of aquifers and the kind and nature of the material in each stratum penetrated. Show at least one entry for each change in formation.		
Material	From	To
TOP SOIL	0	2
DECOMPOSED GRANITE	2	78
BROWN CLAY	78	146
DECOMPOSED GRANITE	146	158
LIGHT GREY GRANITE	158	213
LIGHT BROWN GRANITE	213	430
LIGHT GREY GRANITE	430	465
LIGHT BROWN GRANITE	465	507
DARK REDDISH BROWN GRANITE	507	516
GREY GRANITE	516	548
LIGHT BROWN GRANITE	548	565
SOFT BROKEN GRANITE W/WATER	565	576
LIGHT BROWN GRANITE	576	588


Notes:

Work started 05/18/2010 Completed 05/24/2010

WELL CONSTRUCTION CERTIFICATION:
 I constructed and/or accept responsibility for construction of this well and its compliance with all Washington well construction standards. Materials used and the information reported are true to my best knowledge and belief.

☒ Driller ☐ Engineer ☐ Trainee

Name: SAM BEARDSLEE License No.: 2805

Signature: 

If trainee, Licensed driller is:	License No.:
Licensed Driller Signature:	

Drilling Company:
 NAME: FOGLE PUMP & SUPPLY, INC. Shop: COLVILLE
 ADDRESS: 316 W. 5TH
 Colville, WA 99114
 Phone: 509-684-2569 Toll Free: 800-533-6518
 E-Mail: jeanne@foglepump.com
 FAX: 509-684-3032 WEB Site: www.foglepump.com

Contractor's
 Registration No.: FOGLEPS095L4 Date Log Created: 05/26/2010

WELL TESTS: Drawdown is amount water level is lowered below static level.					
Was a pump test made? No If yes, by whom					
Yield:	gal/min with	ft drawdown after			
Yield:	gal/min with	ft drawdown after			
Yield:	gal/min with	ft drawdown after			
Recovery data (time taken as zero when pump turned off)(water level measured from well top to water level)					
Time:	Water Level	Time:	Water Level	Time:	Water Level
Date of test:					
Bailer test	gal/min	ft drawdown after	hrs.		
Air test 20+	gal/min w/ stem set at	600 ft. for 1	hours		
Artesian flow	gpm	Date			
Temperature of water	Was a chemical analysis made No				