

WATER WELL REPORT

State of Washington Date Printed 26 Nov 2003 Log No
Construction/Decommission Original Construction 24203
Construction Notice of Intent # 143818

CURRENT

Notice of Intent No
Unique Ecology Well I D No
Water Right Permit Number

Amendment
Secretary missed
liner when she
submitted
W173863
AHG423

OWNER GLASER ROBERT

OWNER ADDR 1497 B PRITCHARD RD EVANS WA 99126

Well Street Address

City

County STEVENS

Location SE 1/4 SE 1/4 Sec 2 T 37 R 38E EWM

Lat/Long

Lat Deg

Lat Min/Sec

(s t r still

Long Deg

Long Min/Sec

REQUIRED)

Tax Parcel No 1955501

CONSTRUCTION OR DECOMMISSION PROCEDURE

Formation Describe by color character size of material and structure Show thickness of aquifers and the kind and nature of the material in each stratum penetrated Show at least one entry for each change in formation

Material


From

To

TOPSOIL	0	3
SAND BROKEN ROCK W/COBBLES	3	28
GRAY SAND CLAY MOIST	28	37
GRAY SHALE SOFT	37	42
GRAY SHALE MEDIUM	42	125
GRAY SHALE SOFT W/QUARTZ	125	210
GREEN SHALE W/QUARTZ SOFT	210	218
GRAY SHALE W/QUARTZ MEDIUM	218	382
LT GRAY SHALE W/QUARTZ SOFT TO MEDIUM	382	400
GRAY SHALE W/QUARTZ	400	610
SHALE W/PYRITE	610	612
GRAY SHALE W/QUARTZ	612	620

Notes

1/4 1/2 GPM TOTAL CUSTOMER REFUSED LINER



Work started 07/30/2003

Completed 07/31/2003

WELL CONSTRUCTION CERTIFICATION

I constructed and/or accept responsibility for construction of this well and its compliance with all Washington well construction standards Materials used and the information reported are true to my best knowledge and belief

☒ Driller ☐ Engineer ☐ Trainee

Name RONALD HURN License No 2258

Signature *Ronald Hurn*

If trainee Licensed driller is License No

Licensed Driller Signature

Drilling Company

NAME FOGLE PUMP & SUPPLY INC

Shop COLVILLE

ADDRESS 316 W 5TH

Colville WA 99114

Phone 509-684 2569 Toll Free 800-533-6518

E Mail jrs@foglepump.com

FAX 509 684 3032 WEB Site www.foglepump.com

Contractor's

Registration No FOGLEPS095L4

Date Log Created 08/04/2003

PROPOSED USE DOMESTIC			
TYPE OF WORK Owners s Well Number (If more than one well) 3			
NEW WELL Method ROTARY			
DIMENSIONS Diameter of well 6 inches			
Drilled 620 ft Depth of completed well 620 ft			
CONSTRUCTION DETAILS		Casing installed WELDED	
Liner installed		6 Dia from +2 ft to 42 ft	
4 Dia from 5 ft to 585 ft		Dia from ft to ft	
Dia from ft to ft		Dia from ft to ft	
Perforations Yes Used In Liner			
Type of perforator used SKILL SAW			
SIZE of perforations 6 in by 1/4 in			
200 Perforations from 100 ft to 585 ft			
Perforations from ft to ft			
Perforations from ft to ft			
Screens No K Pac Location			
Manufacture s Name			
Type Model No			
Diam slot size from ft to ft			
Diam slot size from ft to ft			
Gravel/Filter packed No Size of Gravel			
Material placed from ft to ft			
Surface seal Yes To what depth 19 ft			
Seal method Material used in seal BENTONITE			
Did any strata contain unusable water? No			
Type of water Depth of strata			
Method of sealing strata off			
PUMP Manufacture s name			
Type H P 0			
WATER LEVELS Land surface elevation above mean sea level 0 ft			
Static level 200 ft below top of well Date 07/31/2003			
Artesian Pressure lbs per square inch Date			
Artesian water controlled by			
WELL TESTS Drawdown is amount water level is lowered below static level			
Was a pump test made? No If yes by whom?			
Yield gal/min with ft drawdown after			
Yield gal/min with ft drawdown after			
Yield gal/min with ft drawdown after			
Recovery data (time taken as zero when pump turned off)(water level measured from well top to water level)			
Time	Water Level	Time	Water Level
Date of test			
Bailer test 25 gal/min 619 ft drawdown after 1 hrs			
Air test 0 gal/min w/ stern set at ft for hours			
Artesian flow gpm Date			
Temperature of water Was a chemical analysis made? No			